

City of Fayetteville Building Safety Division

POLICY & PROCEDURE

Natural Gas Inspection Banding Tape

As discussed and agreed with Russell Anderson, Arkansas Western Gas Co., beginning 10-23-95 taping of gas lines will be as follows:

1-yel= line tight at meter or building as air tested. That is, 1-yellow on riser at meter means that the underground line at building has been air tested tight; 1-yellow on line at building means that the lines in the building has been air tested tight.

3-yel= underground line and all lines in building have been air tested tight and all gas appliances and gas fired equipment has been inspected as safe and a temporary gas meter may be installed and all appliances and equipment may be tested to determine safety and correct operations.

1-grn= all lines have been air tested tight and have at least 1-yel on riser at meter or required air test on line and all appliances and equipment inspected as safe for new construction. Or a gas line replacement and/or gas appliance replacement that has been permitted has been inspected as safe. A permanent meter may be installed.

A temporary meter will be deemed permanent when a Certificate of Occupancy is executed and issued or when alterations or repair has been inspected as safe and passed the final inspection.

Situations not covered shall be worked out with the gas company on a case by case basis.

Approved By



Building Official

October 8, 1996